

DUDLEY KNOX LORARY NAVAL POSTGRADUATE SCHOOL MONTEREY CA 93943-5101









Approved for public release; distribution is unlimited.

Design of a Cold-Flow Test Facility for the High-Pressure Fuel Turbopump Turbine of the Space-Shuttle Main Engine

by

Colin C. Studevan Lieutenant, United States Navy B.S., U.S. Naval Academy, 1985

Submitted in partial fulfillment of the requirements for the degree of

MASTER OF SCIENCE IN ASTRONAUTICAL ENGINEERING

from the
NAVAL POSTGRADUATE SCHOOL
December 1993

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

AGENCY USE ONLY (Leave blank)	2 DEPORT DATE	3. REPORT TYPE AN	D DATES COVERED
AGENCI OSE ONE! (LESVE BISIN)	1993, December	Master's T	
	, =====================================	master s r	
TITLE AND SUBTITLE			5. FUNDING NUMBERS
DESIGN OF A COLD-FLO			
HIGH-PRESSURE FUEL ?	TURBOPUMP TURBINE	OF THE	
SPACE-SHUTTLE MAIN I	ENGINE		
AUTHOR(S)			
Colin Charles Studes	van		
PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)		8. PERFORMING ORGANIZATION
PERFORMING ORGANIZATION NAME	3) AND ADDRESS(ES)		REPORT NUMBER
Marral Doctored design	7 -1 7		
Naval Postgraduate S			
Monterey, Ca 93943-5	000		
SPONSORING/MONITORING AGENCY	NAME(S) AND ADDRESS(ES)		10. SPONSORING / MONITORING
			AGENCY REPORT NUMBER

11. SUPPLEMENTARY NOTES

The views expressed in this thesis are those of the author and do not reflect the official policy or position of the Department of Defense or the U.S. Government.

12a. DISTRIBUTION / AVAILABILITY STATEMENT

Approved for public release; distribution is unlimited.

12b. DISTRIBUTION CODE

13. ABSTRACT (Maximum 200 words)

The design and installation at the Naval Postgraduate School of a cold-flow test facility for the turbine of the high-pressure fuel turbopump of the Space Shuttle Main Engine, is reported. The specific article to be tested is the "Alternate Development Model" designed and manufactured by Pratt & Whitney. The design of individual components is documented. The installation of the facility subsystems is described in detail. A preliminary estimation of turbine performance is made.

14. SUBJECT TERMS Turbi Development Mod	DEJECT TERMS Turbine Test Rig, Alternate Turbopump Development Model, SSME Turbopump Turbine						
17. SECURITY CLASSIFICATION OF REPORT	18. SECURITY CLASSIFICATION OF THIS PAGE	19. SECURITY CLASSIFICATION OF ABSTRACT	20. LIMITATION OF ABSTRACT				
Unclassified	Unclassified	Unclassified	Unclassified				

ABSTRACT

The design and installation at the Naval Postgraduate School of a cold-flow test facility for the turbine of the high pressure fuel turbopump of the Space Shuttle Main Engine, is reported. The specific article to be tested is the "Alternate Development Model" designed and manufactured by Pratt & Whitney. The design of individual components is documented. The installation of the facility subsystems is described in detail. A preliminary estimation of turbine performance is made.

TABLE OF CONTENTS

I.	INTR	ODUCTION	• •	• •	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	1
II.	. FAC	ILITY DES	SIGN	AND	INS	STAI	LLA	TI	01	ī	•		•					•		4
	Α.	AIR SUPI	PLY S	YSTE	EM .		•	•	•	•	•	•	•	•	•	•	•	•	•	4
	В.	TURBINE	ASSE	MBL	Ζ.	•	•	•	•	•	•	•		•	•	•	•		•	7
	c.	HYDRAUL	IC DY	NAMO	DMET	ER	•	•	•	•	•	•	•	•	•	•	•	•	•	12
	D.	LUBRICAT	NOIT	SUBS	SYSI	EM	•	•	•	•	•	•	•	•	•	•	•	•	•	19
	E.	CONTROL	AND	INST	TRUM	IENT	TAT	'IC	N	•	•	•	•	٠	•	•	•	•	•	19
III	I. PE	RFORMANCI	E EST	'IMA'	TION	1.	•	•	•	•	•	•	٠	•	•	٠	٠	•	•	26
IV.	. CON	CLUSIONS	AND	RECO	OMME	ENDA	ATI	ON	S	•	•	•	•	•	•	•	•	•	•	27
	A.	CONCLUS	IONS	• •		•	•	•	•	•	•	•	•	•	•	•	•	•	•	27
	В.	RECOMMEN	ITADN	ONS	• •	•	•	•	•	•	•	•	•	•	•	•	•	•	•	28
API	PENDI	X I. ENG	INEER	RING	DRA	AWIN	IGS	}	•	•	•	•	•	•	•	٠	•	•	•	29
AP	PENDI	x II	• •	• •	• •		•	•	•	•	•	•	•	•	•	•	•	•	•	42
LIS	ST OF	REFEREN	CES		•		•	•	•	•	•	•	•	•	•	•	•	•		44
TN.	TTTAL	DISTRIB	UTTON	I LIS	ST .															45

LIST OF FIGURES

Figure	1.	Allis-Chalmers Compressor
Figure	2.	Air Supply for the High Speed
		Laboratory
Figure	3.	TTR Layout
Figure	4.	Test Rotor with Sample Blading
Figure	5.	Bearing Sleeve Assembly
Figure	6.	Hydraulic Dynamometer
Figure	7.	Schematic of the Automatic Dynamometer
		Load Control System
Figure	8.	Fifty-Gallon Holding Tank and Pump 18
Figure	9.	Portable Turbine Lubrication Unit 2
Figure	10.	Bearing Lubrication Path
Figure	11.	Inlet and Outlet Control Valves
Figure	12.	TTR Control Console



I. INTRODUCTION

The purpose of this report is to describe the design and installation at the Naval Postgraduate School's Turbopropulsion Laboratory (TPL), of a cold-flow test facility for a high-work turbine. The test turbine, intended to power the liquid fuel pump on the Space Shuttle Main Engine (SSME), was designed and manufactured by Pratt & Whitney (P&W) as the Alternate Turbopump Development (ATD) model. The original High-Pressure Fuel Turbopump (HPFTP) for the SSME was designed and manufactured by Rocketdyne. The HPFTP consists of a high pressure hydrogen pump driven by a two-stage, axial-flow turbine. The turbine is a low-pressure ratio reaction turbine driven by a mixture of steam and gaseous hydrogen. The turbine produces approximately 73,000 hp. At its design point, the turbine operates with an inlet temperature of about 1,900°R and an inlet pressure of approximately 5,200 psi.

NASA's Marshall Space Flight Center established a "cold-flow" testing facility to experimentally determine the performance of the SSME HPFTP. The facility was a short-duration, blow-down rig, and the turbine was spun up to speed prior to activating the airflow. Hudson et al [Ref. 1] performed the first tests on the Rocketdyne HPFTP. Subsequent testing of the Pratt & Whitney ATD HPFTP was conducted by

Gaddis et al [Ref. 2] for "back-to-back" comparisons with the Rocketdyne HPFTP. The turbine performance and turbine parameters such as airfoil surface static pressure distributions, static pressure drop through the turbine, and exit swirl angle were investigated at the design point, over its operating range, and at extreme off-design points. In the present work, following a program of tests using only a single stage, two-stage performance data will be obtained and compared with those reported by Gaddis.

The purpose of the present installation was not primarily for performance measurements. Rather, it was to continue and extend a program of time-resolved flow measurements turbomachines for the purposes of both evaluating advanced designs and validating viscous flow analysis codes. complex turbine test rig (TTR) at TPL, last reported by Kane (1978) and Eargle (1980), was not suited for this purpose. The rig was expressly designed not to require interblade measurements, could not readily allow access for optical measurements, and the turbine stages available for the rig were of no current interest. The rig was therefore removed from the test cell, and the installation described in the present document was put in its place. Where possible, components of the old rig were refurbished and reused (air supply system, hydraulic dynamometer, test table and rotor support), however the installation was a complete redesign and required the manufacture, installation and alignment of all

components between the flange from the air supply system and the drive shaft to the dynamometer.

In the present document, the design and installation of the new turbine test facility are described. Chapter III gives results of some preliminary performance predictions for the rig. Chapter IV contains conclusions and recommendations. Engineering drawings and other system documentation are contained in the Appendices. It is noted that the present documentation was completed prior to initial tests to check out the installation.

II. FACILITY DESIGN AND INSTALLATION

A. AIR SUPPLY SYSTEM

Air to drive the HPFTP turbine was supplied by an Allis-Chalmers twelve-stage axial compressor. The compressor is driven by a 1250 horsepower electric motor; at a rotational speed of 12,000 revolutions per minute, pumping a maximum volume flow rate of 10,000 cubic feet per minute, to a maximum pressure ratio of 3 to 1. The Allis-Chalmers compressor is shown in Figure 1. The air supply system arrangement for the High Speed Laboratory of the TPL and the test cell is shown in Figure 2.

During normal operation, air enters the compressor through a filtered intake open to the atmosphere. The air then passes through the 12-stage axial compressor, and enters the aftercooler where the air is cooled to about 110°F. Before leaving the compressor room, the air flows through a flow metering orifice in the facility supply line. After entering the TTR the air flows through a manually-controlled butterfly valve, before entering the TTR plenum chamber. The air supply from the plenum chamber is remotely controlled by a motor-driven butterfly valve. The air exits the plenum chamber through an eight-inch pipe, passes through an eight-to-ten




Figure 1. Allis-Chalmers Compressor




Figure 2. Air Supply for the High Speed Laboratory

inch pipe expander, and flows into the turbine inlet piping. A two-degree taper was machined on the inside surface of the inlet piping which mated flush against the inlet strut housing of the test turbine. Access holes were drilled at 120° around the inlet piping for installing performance instrumentation such as inlet total pressure and temperature probes. Engineering drawings of the inlet piping are contained in Appendix I.

B. TURBINE ASSEMBLY

High pressure air from the inlet piping, flows through the inlet strut housing into the turbine as shown in Figure 3. The air then flows axially into the first stage stator which imparts swirl to the flow. The swirling airflow is turned through the rotor, which produces shaft power, before exhausting into the test cell. The shaft power is absorbed by a water dynamometer, shown schematically in Figure 3.

The HPFTP test specimen was supplied by Pratt and Whitney. The components which were supplied included the inlet-strut housing, the test rotor, the first and second stage stator and rotor blades, the outer casing, and the retainer ring for the first stage stator.

The remaining components that were needed to complete the test facility were either designed and machined, or were purchased from commercial vendors. Drive-shaft components which were designed included the main bearing shaft, the




Figure 3. TTR Layout

bearing sleeve, the bearing spacers and retainer rings, and the oil seals. Component diagrams are contained in Appendix I.

The test rotor consisted of a single stainless-steel disk with fifty "fir tree" slots broached along the entire length to accommodate an equal number of first and second stage rotor blades, tabs, and pan weights. The slots were marked and numbered clockwise from 1 to 50 when looking forward from the rear. The blades were separated by tabs and pan weights and were held in place by spring loaded retainer rings on each end of the rotor disk. The pan weights had labyrinth knife edges which formed the seal underneath the shrouded hub of the second-stage stator. A view of the rotor is shown in Figure 4.

Each of the first stage rotor blades was weighed and then mounted so that blades with equivalent mass were positioned 180 degrees apart. The pan-weight spacers were mounted in identical fashion. P&W supplied TPL with two sets of second stage blading. Initial testing of the turbine was intended to use only the first stage stator and rotor. To safely interlock the blading on the rotor disk, the extra set of second stage blades were cut off at the root and ground to be equivalent in height and weight. The blades, tabs, and pan weights fed easily and securely into the "fir tree" grooves on the rotor disk.




Figure 4. Test Rotor with Sample Blading

When mounting these components on the rotor disk, care had to be taken to ensure a correct fit. The components were machined to self-lock once in place. To mount correctly, components were initially slipped into place so that only 1/8" was inserted into the groove. Then, moving clockwise (looking forward from the rear), each blade, tab, or pan weight was slipped into the 1/8" position sequentially until all components of that row were similarly mounted. Once all components of that row were inserted 1/8" into the groove, each blade was slowly moved forward, in sequence, until all components of that row were in their most forward position (Fig. 4). An exact listing of individual blade positions is given in Appendix II.

The main shaft was designed to separate aft of the flange which was bolted to the test rotor (Fig. 3). This was done to facilitate the mounting of all components into the bearing housing sleeve. The shaft incorporated a 3/16" diameter hole which extended through the flange and the shaft so that once in place a lock pin could be installed. There were two bearing surfaces along the length of the shaft, one forward and one aft. The Fafnir high-precision bearings were mounted to the bearing shaft in pairs. Each bearing was marked with a thrust point on the outer and inner races. Following manufacturer's recommendations for proper installation, each pair of bearings was mounted so that the outer race thrust points were aligned and faced together and the inner race

thrust points were aligned and faced away from each other as shown in Figure 5.

During assembly, the flange was separated from the main bearing shaft. The first pair of bearings was inserted onto the shaft from the aft end and moved forward to rest against the retainer flange forward of the bearing surface. bearing inner spacer was then inserted onto the shaft so that it rested against the inner race of the first set of bearings. The bearing outer spacer was inserted over the bearing inner spacer so that its edges rested against the outer race of the bearing. The second pair of bearings was then slipped onto the aft bearing surface of the shaft until the inner race of the bearing rested against the bearing inner spacer (Fig. 5). The oil-flinger was mounted onto the shaft against the inner race of the second set of bearings. A circular locking nut was used at the end of the shaft to secure the components onto the shaft. The entire assembly was inserted into the main bearing sleeve. Bearing retainers were then secured to each end of the sleeve. Installation of the oil-seals over the bearing retainers completed the main-bearing sleeve assembly.

C. HYDRAULIC DYNAMOMETER

The energy output of the turbine was designed to be absorbed by a 250-horsepower Series 061 hydraulic dynamometer manufactured by Kahn Industries, as shown in Figure 6. A




Figure 5. Bearing Sleeve Assembly




Figure 6. Hydraulic Dynamometer

schematic of the automatic load control system is shown in Figure 7. The dynamometer consisted of one perforated disk enclosed in a housing which rotated between similar sets of perforated stators. In the Kahn design, cold water enters the rotor chamber at the center. The water is accelerated by the rotating disc and thrown outward by centrifugal action. From the outer diameter of the rotor chamber inward, the water forms an annulus which rotates at approximately half of the angular disc speed. The resulting centrifugal pressure discharges the water through a radial hole at the bottom of the housing. Power is absorbed by vortices created in the rotor and stator holes. The resulting drag acts as a resistance to rotation and tends, with an equal torque, to turn the dynamometer housing. The power absorbed by the dynamometer is a function of rotor speed and of the water level in the rotor chamber.

As shown in Figure 7, the water level in the dynamometer is regulated by a set of Fischer control valves located at the water inlet and outlet lines. Opening of the inlet control valve or closing of the outlet control valve causes the water level to increase. Closing of the inlet control valve or opening of the outlet control valve causes the water level to decrease. Power absorption by the dynamometer gives rise to an increase in water temperature. In order to remove the heat, a continuous flow of water through the dynamometer is required.




Figure 7. Schematic of the Automatic Dynamometer Load Control System

The present installation was changed from the installation described in Kane (Ref. 3) because changes had been made in the water cooling system for the Allis-Chalmers compressor. Water was supplied to the dynamometer, from the Allis-Chalmers cooling system, at a constant pressure of 50 psi. It entered the inlet control valve, flowed through the dynamometer housing, and exited through the outlet control valve and dumped into a fifty gallon holding tank at atmospheric pressure. The water was then pumped back into the pressurized, closed-loop system by a Gould nine-stage centrifugal pump located at the base of the holding tank.

The water level in the holding tank was set by the position of three electronic probes, which were inserted into the top of the holding tank, as shown in Figure 8. The probes were connected to a Warrick controller which controlled the on-off cycle of the Gould 9-stage pump. These probes were set so that the pump switched to the ON position when the water level reached the desired high point, and switched OFF when it reached the desired low point. The low point was chosen to avoid running the holding tank dry and damaging the pump. Initial testing of the system revealed that the cyclic operation of the pump had a adverse effect on the ability of the system to maintain a constant pressure. Continuous operation of the pump, by controlling the rate at which the water was returned to the closed-loop system, corrected the problem, and enabled the system to maintain a constant




Figure 8. Fifty-Gallon Holding Tank and Pump

pressure. To control the rate of water return, a manually-controlled restriction valve was installed downstream of the Gould water pump. By maintaining a near constant level in the holding tank, the system pressure remained constant.

D. LUBRICATION SUBSYSTEM

Lubrication for the high precision bearings was provided by a Portable Turbine Lubrication Unit (PTLU). The unit is shown in Figure 9. Oil entered through an opening located atop and aft on the bearing sleeve, as shown in Figure 10. The oil then flowed through openings in the outer bearing spacer, passed through the bearings, and exited from two openings located on the bottom of the oil seals. The oil was collected and returned to the reservoir of the PTLU.

E. CONTROL AND INSTRUMENTATION

The speed control was unchanged from that described by Kane (Ref. 3). Control for the hydraulic dynamometer was provided by a Fischer-Porter electronic setpoint controller (Fig. 7). The controller received a conditioned feedback signal from the dynamometer, via a magnetic speed pickup, and compared it with the speed setpoint. When the feedback signal deviated from the setpoint, the controller produced a corrective signal which opened or closed the outlet control valve, until the deviation became zero, and the feedback signal coincided with the setpoint. The controller could be




Figure 9. Portable Turbine Lubrication Unit




Figure 10. Bearing Lubrication Path

set to automatic or operated manually. The inlet-control valve was used to adjust the water flow rate for a particular power range, and was manually controlled. Figure 11 shows the TTR test cell looking forward from the rear. The inlet control valve is shown at the lower left position, the dynamometer in the center, the outlet control valve at the upper right. Both the inlet and outlet control valves incorporated pneumatic valve positioners attached to the valve bodies. Connections were made using 3/8" O.D. copper transmission lines. Supply pressure was set at 20 psi gauge. References 5 and 6 contain specific guidelines for setting control modes on the electronic controller.

The dynamometer was instrumented to provide output power measurements. Two thermocouples were mounted in the water lines, upstream and downstream of the dynamometer. Temperature readouts were given on the system control panel shown in Figure 12. The instrument in the upper left corner gave time histories of the dynamometer inlet and outlet temperatures. The instrument in the lower left corner allowed selection of the desired channel to monitor the dynamometer inlet or outlet water temperatures. Dynamometer parameters are listed below:

OPERATING RANGE

Max Capacity 250 HP
Max Speed 19,000 RPM
Max Torque 75 FT. LBS




Figure 11. Inlet and Outlet Control Valves




Figure 12. TTR Control Console

WATER SUPPLY REQUIREMENTS

Water Flow @ Delta T= 76°F 4 GPH/HP
Supply Pressure 50 psig
Max Inlet Temp 80° F
Max Outlet Temp 156° F

A water flowmeter was also installed upstream of the dynamometer inlet. Power measurements are normally determined from readouts taken from a Lebow load cell mounted on the dynamometer housing (which measure torque input) and RPM measurements taken from the magnetic speed pickup. The measurement of water flow rate and temperature rise was to provide a redundant check on the measurement of power.

III. PERFORMANCE ESTIMATION

The power output (P) of the turbine was estimated using the expression

$$P = \frac{m^2 R T_o 2\pi N r}{A_o p_o 60} (\tan a_1 - \tan a_2)$$
 (1)

where p_0 is the total pressure, T_0 the total temperature, N the rotor speed, \underline{m} the mass flow rate, r is the meanline radius, a_1 is the absolute flow-angle into rotor, a_2 is the absolute flow-angle out of rotor, and A_0 is the annulus cross-sectional area.

Equation (1) was derived using the Euler turbine equation, with the assumption of constant density, as described in Reference 7. Specifying

p _o =279 kPa	T _O =288 K
N=7500 RPM	r=0.11684 m
\underline{m} =6.5 kg/sec	a _l =71°
A _O =0.02231 m2	a ₂ =-46.75°

the power for the single-stage axial turbine was estimated at 212 kW, which is equal to approximately 283 horsepower.

IV. CONCLUSIONS AND RECOMMENDATIONS

A. CONCLUSIONS

A test rig has been designed for the High Pressure Fuel Turbopump turbine of the Space Shuttle Main Engine. Inlet piping was designed, fabricated, and installed to connect the air supply to the turbine. Provisions were made for turbine inlet instrumentation.

A single stage of the two-stage Pratt & Whitney "Alternate Turbopump Development" model was assembled and installed on a steel table within the test cell. The shaft and bearing housing between the rotor and the hydraulic dynamometer were designed, manufactured, and installed. The dynamometer was refurbished and the speed control system was commissioned. The upgraded cooling water system for the laboratory's Allis-Chalmers (A/C) compressor required the addition of a pump to recirculate the coolant. The control system instrumentation was checked for integrity and functionality. An existing recirculating oil system was used for bearing lubrication. performance estimate of the single-stage turbine was made based on the pressure and temperature supplied by the A/C The power output was within the operating compressor. envelope of the dynamometer. Problems encountered during balancing of the rotor and bearing housing assembly prevented initial test operation of the system.

B. RECOMMENDATIONS


The following are recommended:


- 1. Install instrumentation for bearing temperature and vibration measurements.
- 2. Incorporate a mass-flow measurement device in the turbine air supply so that air from the A/C can be bypassed as a means of setting turbine inlet pressure.
- 3. Include more extensive instrumnetation for performance measurements.
- 4. Design and manufacture a new casing for LDV measurements which includes optical access windows over the rotor blades.


APPENDIX I.


This appendix contains engineering diagrams for the TTR inlet piping and bearing housing components. Contents include:


DRAWING	PAGE	ИО
Inlet Piping	30	
Inlet Flange	31	
Bearing Housing Assembly	32	
Shaft	33	
Bearing Housing Sleeve	34	
Bearing Retainer Ring	35	
Bearing Outer Spacer	36	
Bearing Inner Spacer	37	
Oil Seal Front	38	
Oil Seal Rear	39	
Oil Flinger	40	
Retainer Nut	41	
































APPENDIX II.

This appendix contains the first-stage rotor blades and pan weight positions. Items are listed by their identification number (I.D.), position (POS), and weight (WT) in grams.

First Stage Rotor Blades:

I.D. A-79 I-92 G-92 K-62 J-91 L-63 D-95 K-47 K-60 L-85 A-62 M-60 L-60 K-64 G-55 E-73 B-61 O-85 O-95	POS 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 22	WT 34.9489 34.8078 34.7565 34.5687 34.5205 34.4888 34.4589 34.4519 34.4519 34.4137 34.4106 34.3963 34.3468 34.3377 34.3225 34.2797 34.2196 34.1111 34.0786 34.0527 34.0145	I.D. I-86 L-79 J-76 C-55 F-61 B-62 H-57 B-55 C-98 G-106 O-80 G-47 L-77 O-60 H-91 K-104 L-55 K-100 A-81 A-41 L-61 O-75	POS 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47	WT 34.9148 34.7939 34.7215 34.5642 34.5215 34.4945 34.4881 34.4571 34.4495 34.4267 34.4134 34.4060 34.3590 34.3455 34.3071 34.3103 34.2578 34.1478 34.0956 34.0728 34.0486 34.0092
J-55 P-55	22	34.0145	0-75 M-81	47	34.0092
I-70	24	33.7000	M-81 K - 32	49	33.6408
A-65	25	33.5672	A-106	50	33.5588

Pan Weights:

LIST OF REFERENCES

- 1. Hudson, S. T., Gaddis, W.S., and Johnson, J.L., "Cold Flow Testing of the Space Shuttle Main Engine High Pressure Fuel Turbine Model," AIAA Paper No.91-2503, paper presented at the American Institute of Aeronautics and Astronautics 27th Joint Propulsion Conference, Sacramento, California, 24-26 June 1991.
- 2. Gaddis, S.W., Hudson, S.T., and Johnson. P.D., "Cold Flow Testing of the Space Shuttle Main Engine Alternate Turbopump Development High Pressure Fuel Turbine Model," ASME Paper No. 92-GT-280, paper presented at the International Gas Turbine and Aeroengine Congress and Exposition, Cologne, Germany, 1-4 June 1992.
- 3. Kane, W. J., Experimental Investigation of the Effects of Rotor to Stator Axial Spacing on the Performance of A Single Stage Transonic Axial Turbine, M.S.M.E. Thesis, Naval Postgraduate School, Monterey, Ca, 1978.
- 4. Eargle, T.P., Evaluation of Factors Affecting
 Repeatability and Accuracy of Turbine Rig Test Results,
 M.S.A.E. Thesis, Naval Postgraduate School, Monterey,
 Ca, 1980.
- 5. <u>Instruction Manual Waterbrake Dynamometer</u>, Model 061-109, Kahn Companies, No. 9755, 1976.
- 6. <u>Instruction Manual Automatic Dynamometer Speed Control System</u>, Kahn Industries, No. 1766A, 1976.
- 7. National Aeronautics and Space Administration, <u>Turbine</u>
 <u>Design and Application</u>, by A.J. Glassman, pp. 21-62,
 Government Printing Office, Washington, DC, 1972.

INITIAL DISTRIBUTION LIST

		No	Copies
1.	Defense Technical Information Center Cameron Station Alexandria VA 22304-6145		2
2.	Library, Code 052 Naval Postgraduate School Monterey CA 93943-5002		2
3.	Department Chairman, AA Department of Aeronautics Naval Postgraduate School Monterey, CA 93943		1
4.	Garth V. Hobson, Turbopropulsion Laboratory Code AA/Hg Department of Aeronautics Naval Postgraduate School Monterey, CA 93943		7
5.	Naval Air Systems Command AIR-536T(Attn: Mr. Paul F. Piscopo) Washington, District of Columbia 20361-5360		1
6.	Naval Air Warfare Center Aircraft Division (Trenton) PE-31(Attn: S. Clouser) 250 Phillips Blvd Princeton Crossroads Trenton, NJ 08628-0176		1
7.	Colin C. Studevan 2110 Glenwood Av Toledo, OH 43620		1











